

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21808-00-00
Spot: NENENW Sec/Twnshp/Rge: 18-13S-21W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: WERTH B Well #: 1
County: TREGO Total Vertical Depth: 4062 feet

Operator License No.: 33069
Op Name: ENCORE OPERATING COMPANY
Address: 1601 BLAKE STREET, SUITE 500
DENVER, CO 80202

PROD Size: 5.5 feet: 4060 w/435 sxs cmt
SURF Size: 8.625 feet: 247 w/175 sxs cmt

132⁰²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2004 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: ROLLAND NYP Company: ENCORE OPERATING COMPANY Phone: (785) 737-3242

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 500# hulls.
ACO-1 indicates 5 1/2" cemented to surface with 435 sxs.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2004 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Hooked up to the annulus and pumped 20 sxs cement
S.I.P. 500#.
TIH with tubing to 3000' - mixed and pumped 140 sxs cement with 400# hulls.
Pulled up to 1500' - circulated cement with 120 sxs cement with 100# hulls.
POOH. Topped with 25 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

170
INVOICE
DATE 4.27.04
2004061466
(TECHNICIAN)

Form CP-2/3

APR 21 2004

TRIPLE 'H' OIL OPERATIONS

P.O. BOX 248

HAYS, KS. 67601


#1 WERTH-B

18-13-21W

NE NE NW

CONTR DRELLING OIL, INC. CTY TREGO

GEOL JACK CHILDERS FIELD RIGA NW EXT
(1/8 W)



ELV 2246 KB SPD 11/18/85 CARD ISSUED 3/13/86 IP P 22 BO & 26 BWPD
2247 GL DRLG COMP 11/26/85 MARM 3930-3970

SMP	Tops	Depth/Datum
TOP	3315-1069
HEEB	3563-1317
TOR	3585-1339
LANS	3600-1354
MARM	3928-1682
CONG	3976-1730
RTD	4062-1816

API 15-195-21,808

8 5/8 " 247 / 175SX, 5 1/2 " 4060 / 285SX
 DST (1) 3621-3666 (LANS) / 30-30-10-30, REC 20' M, W / VERY
 FEW OIL SPKS IN TOOL, SIP 963-997#, FP 55-55 / 55-55#
 DST (2) 3754-3820 (LKC) / 30-30-30-30, REC 20' M, SIP 231-
 91#, FP 55-55 / 66-66#
 MICT - CO, PF (MARM) 3930-3970, W / 1 SPF, AC 3000 GAL
 (15% MCA) & 1500B KCL WTR OVERFLUSH, SWB DWN, SO,
 POP, P 22 BO & 26 BWPD, 1/786

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

INDEXED

DATE
 BY