

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03683-00-00  
Spot: SESENW Sec/Twnshp/Rge: 9-16S-14W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: NUSS Well #: 1  
County: BARTON Total Vertical Depth: 3414 feet

Operator License No.: 3273  
Op Name: LOEB, HERMAN L.  
Address: PO BOX 524  
LAWRENCEVILLE, IL 62439

PROD Size: 5.5 feet: 3410 300 SX CMT  
SURF Size: 8.625 feet: 178 175 SX CMT

85  
# 221

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/21/2004 10:00 AM

Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.

Proposal Rcvd. from: ML COX Company: LOEB, HERMAN L. Phone: (620) 786-2009

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
DV at 601' set with 200 sxs cement.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/21/2004 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1650' - 920' - 430'.  
Swaged onto 5 1/2" - mixed and pumped 285 sxs cement with 500# hulls.  
Max. P.S.I. 800#. S.I.P. 300#.  
Hooked up to the annulus and pumped 5 sxs cement.  
S.I.P. 500#.

RECEIVED  
APR 26 2004  
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
3360	3364		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED  
DATE 4-26-04  
NO. 2004061465

APR 22 2004

HELMERICH & PAYNE

#1

NUSS

9-16-14W  
SE SE NW

52

Contr. INTERSTATE DRILLING

BARTON

County

E 1943 RB Comm 7/27/62.

Comp. 9/6/62

IP 85 BOPD, NW

LANS 3360-64

LOG Tops	Depth	Datum
HEEB	3085	-1142
TOR	3102	-1159
LANS	3152	-1209
B/KC	3376	1433
CONG CHT	3378	-1435
ARB	3406	-1463
LTD	3410	-1467
TD	3414	-1471

Casing

8" 178/175 sx  
5" 3410

DST 3159-3201/50", 1440' G, 70'  
H OCM, 300' MDY O, 60' SW,  
BHP 1056-990#/30", FP 73-187#:  
CO: PERF KC 16/3360-64; NS, ACID  
500, SWB 24 BO, NW/1 HR, SWB  
20 BO, NW/1HR:

NUSS


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS