

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02376-00-00
Spot: SENENW Sec/Twnshp/Rge: 18-19S-10W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: WENDELL Well #: 1
County: RICE Total Vertical Depth: 3345 feet

Operator License No.: 31528
Op Name: KELSO, MIKE - OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

PROD Size: 5.5 feet: 3327
SURF Size: 8.625 feet: 250

108 71

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2004 11:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand perforations to 3050' and put 5 sacks of cement on top. Cut off 5-1/2" casing and pull to 1250'. Pump 35 sacks of cement and pull to 900'. Pump 35 sacks of cement and pull to 300'. Circulate cement to surface.

RECEIVED
KCC DISTRICT #2

APR 13 2004

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: PARTIAL

Date/Time Plugging Completed: 04/08/2004 2:30 PM

KCC Agent: VIRGIL CLOTHIER

WICHITA, KS

Actual Plugging Report:

Sanded perforations to 3050' and put 5 sacks of cement on top. Cut off 5-1/2" at 1540' and pulled to 1250'. Pumped 35 sacks of cement and pulled to 900'. Pumped 35 sacks of cement and pulled to 300'. Circulated cement to surface.

60/40 posmix with 4% gel.

Used 100 lbs of cotton hulls at 1250', 900', and 300'.

Perfs:

Top	Bot	Thru	Comments
3310	3316		
3190	3200		
3106	3110		

RECEIVED
KANSAS CORPORATION COMMISSION

APR 26 2004

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENT #13003

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICE

DATE

4-26-04

INV. NO.

200406142