

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20694-00-00
Spot: CW2SWNW Sec/Twnshp/Rge: 3-1S-33W
3300 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: RATHER Well Number: 1
County: RAWLINS Total Vertical Depth: 4548 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

Conductor Pipe: Size feet: 8 1/4 7.81
Surface Casing: Size 8.625 feet: 303 210 SX CMT
Production: Size 4.5 feet: 4258 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/09/2002 2:00 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: SHAWN DEVLIN Company: VIKING RESOURCES, INC. Phone: (316) 262-2502

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 10% gel - 200# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/09/2002 3:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" S.P. set at 303' w/210 sxs cement. 4 1/2" set at 4258' w/150 sxs cement.
4 1/2" production string cut and free at 1730'.
Pulled 4 1/2" to 1550' - pumped 200# hulls and 60 sxs cement.
Pulled 4 1/2" to 320' - pumped 70 sxs cement. Circulated cement to surface.
Pulled 4 1/2" to surface. Topped off with 5 sxs cement.
Plug complete.

RECEIVED
OCT 16 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED Form CP-2/3

DATE 10-16-02
INV. NO. 2003060645

OCT 10 2002

GLEN S. SODERSTROM
DALLAS, TX 75247

3-01 -33W
C W/2 SW NW

#1 RATHER

site: 12-3/4 N & 1 E OF ATWOOD, KS
contr: GOLDEN EAGLE DRILLING
geol: ROGER WELTY
fr date 09/18/87

city: RAWLINS
field: HORINEK

API 15-153-20694

spc date 09/19/87 drig comp 09/27/87 card issued 11/25/87 last revised 11/25/87

ELV: 2989 KB LOG
tops.....depth/datum
ANH.....2822 +167
B/ANH.....2853 +136
TOP.....3692 -703
OREAD.....3819 -830
LANS.....3092 -903
CHER SH.....4322 -1333
ARB WEA.....4483 -1494
RTD.....4548 -1559

IP status:

OIL, P 63 BOPD, NW, LKC 4090-4097,
CSG: 8-5/8" 303 / 210 SX, 4-1/2" 4258 / 150 SX
NO CORES
DST (1) 3965-4010 (LANS), / 30-60-30-60, REC 15' OIL
SPTD M ISIP 906# FSIP 763# IFP 57# -57# FFP 57#
-57# BHT 118 °

(over)

COPYRIGHT 1987
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

WACOICEP