

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-05549-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 27-15S-12W  
4950 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: KAUFMAN B Well #: 1  
County: RUSSELL Total Vertical Depth: 3210 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: PO BOX 2757 202 SOUTH ST. FRANCIS  
WICHITA, KS 67201

PROD Size: 7 feet: 3201 300 SX CMT  
SURF Size: 10.75 feet: 692

# 175 57

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/21/2004 9:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/21/2004 2:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 1335' and 742'.  
Ran tubing to 2763'.  
Pumped 50 sxs 60/40 pozmix - 10% gel cement with 200# hulls.  
Pulled to 2453' and pumped 20 sxs gel with 200# hulls.  
Pulled to 1300' and circulated with 120 sxs cement with 200# hulls.  
Tied onto 7" and pumped 75 sxs cement.  
Max. P.S.I. 300#. S.I.P. 100#.  
Tied onto backside and pumped 5 sxs cement.  
Max. P.S.I. 400#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3017	3023		
2955	2957		
2949	2951		
2944	2946		
2930	2935		
2845	2848		
2777	2780		
2768	2771		

RECEIVED  
APR 29 2004  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

YOP

Signed

Case Morris

INVOICE (TECHNICIAN)

DATE 4-29-04

REV. NO. 2004061474

Form CP-2/3

APR 26 2004

HARRY GORE

#1

KAUFMAN 'B'

27-15-12W  
NW NW NW

Contr.

RUSSELL

County

E 1759

Comm. 8-21-45

Comp. 10-10-45

IP

480 BOPD

Tops	Depth	Datum
ANHY	653	
TOP	2625	
DODGE	2842	
K C	2909	
ARB	3202	
TD	3210	

Casing

15" 35  
6" 3040

SOG & W 2335

1/2 BOPH @ 2666-69

SSO/HFW 2998-3004

50' OPH @ 3056-68

2700' OIH @ 3203-07

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS