

4-031980

8-29

TO: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-153-20,556 00-00

SE NE SW /4 SEC. 04, 01 S, 33 W
1650 feet from S section line
2970 feet from E section line

Operator license# 5363 Lease Horinek well # A-1

Operator: Berexco, Inc. County Rawlins

Address: P.O. Box 723 Well total depth 4210 feet ^{136.82}
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 266 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Berexco, Inc. License# 05363

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 29 Month: August Year: 94

Plugging proposal received from: Paul Brining

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 300 sxs. 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: P.M., Day: 29, Month: August, Year: 94

Actual plugging report: 8 5/8" set @ 266' w/175 sxs. 4 1/2" set @ 4208' w/175 sxs. P.B.T.D. 4160'. Prod. perms. 4054' - 4107'.

Critical area control shots at 2150'. Pumped 50 sxs. cement blend w/50# hulls down 8 5/8". Max. P.S.I. 200#. Shut in. Standing full, pumped 250 sxs. cement blend with 450# hulls down 4 1/2" to Max. P.S.I. 800#. Close in P.S.I. 400#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
OCT 07 1994
CONSERVATION DIVISION
WICHITA, KANSAS
10-7-1994

Remarks: Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES ,CALC X ,NO Dakota plug:YES X ,NO
Plugged through TUBING , CASING . Elevation: GL

I did not observe the plugging. Carl Goodrow

INVOICED
DATE OCT 10 1994
INV. NO. 41363

(agent)
Form CP-2/3