

4-032282

8-21

API Number: 15-153-20,428 -00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

C S2 S2 SW /4 SEC. 05, 01, 33 W  
330 feet from S section line  
3960 feet from E section line

R.L. Arbel  
# 31274

Operator license# 31664 Lease: Palmer Well # B-3  
Operator: Northwest Well Service County: Rawlins 136,44  
Address: 17509 County Road - #14 Well total depth 4198 feet  
Fort Morgan, CO 80701 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 266 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Company Tools License# 31664

Address: 17509 County Road #14 - Fort Morgan, CO 80701

Company to plug at: Hour: A.M. Day: 21 Month: August Year: 1997

Plugging proposal received from: Randy

Company: Northwest Well Service Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.  
Order B.P. and common cement.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 11:30 A.M., Day: 21 Month: August, Year: 1997

Actual plugging report: 8 5/8" set at 266' w/190 sxs cwc. 4 1/2" set at 4197' with 250 sxs  
Prod. Perfs at 4123' - 4129'. Set B.P. at 4060' w/25 sxs common cement on plug. Shots at  
2200' - 1600' and 1200'. Recovered 1200' of 4 1/2" casing. Squeezed 8 5/8" with 80 sxs  
cement blend with 300# hulls. Mixed into Max. P.S.I. 200#. Held. Plug complete.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD  Any plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: \_\_\_\_\_ GL

I  did not observe the plugging.

STATE CORPORATION COMMISSION  
JAN 7 1998  
1-7-98

Carl Goodrow  
(agent)

INVOICED  
DATE JAN 08 1998

INV. NO. 49890  
8-21 JAN 29 1998