

4-041550

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-153-20,036 - 00-00

S2 S2 SE /4 SEC. 06, 01 S, 33 W  
440 feet from S section line  
1320 feet from E section line

Operator license# 5552 Lease Palmer well # 5

Operator: Gore Oil Company County Rawlins

Address: P.O. Box 2757 Well total depth 4185 feet <sup>136.01</sup>  
Wichita, Kansas 67201-2757 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 256 feet  
w/160 sxs.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Halliburton Cementing License#    

Address: Oberlin, Kansas

Company to plug at: Hour: 8:30A.M. Day: 15 Month: December Year: 93

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone:    

Were: 5 1/2" casing set @ 4199' w/1900' sxs. cement. Perf. @ 3838' - 4168'. W.L.M. 4160' - T.O.F. @ 2800'. Casing squeezed from 1415' to TD. Ordered 450 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[     ], Part[ X ], None[     ]

Completed: Hour: 11:30A.M. Day: 15 , Month: December , Year: 93

Actual plugging report: Hooked-up to 8 5/8" casing. Pumped in 100 sxs. cement with 1/4# F.C. Max. 600#. S.I.P. 600#.

Hooked-up to 5 1/2" casing. Pumped in 350 sxs. cement with 500# hulls. Max. 200#. S.I.P. 100#.

Remarks:    

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO    

Bottom plug(in place): YES X , CALC     , NO     Dakota plug: YES X , NO    

Plugged through TUBING     , CASING X . Elevation:     GL    

I did X [ ] did not [ ] observe the plugging.

**INVOICED**

DATE 12-29-93

INV. NO. 39583

Dennis L. Hamel  
(agent) 12-21-93

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 21 1993  
CONSERVATION DIVISION  
Wichita, Kansas