

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

RECEIVED

APR 26 2004

KCC WICHITA

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API #: 15-007-22818-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate sp or completion date

WELL OPERATOR: Anderson Energy, Inc.
(owner/company name)

KCC LICENSE # 6484
(operator's)

ADDRESS: 221 S. Broadway CITY: Wichita

STATE: Kansas ZIP CODE: 67206 CONTACT PHONE: 316-263-1006

LEASE: Prothe WELL#: 1-12 Section 12 Township 33s Range 12w

S/2 SE SW NW SPOT LOCATION/QQQQ COUNTY: Barber

2510 FEET (in exact footage) FROM North LINE OF SECTION (NOT Lease Line)

950 FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8-5/8" SET AT 310 KB CEMENTED WITH 220 SACKS
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 1416 G.L. 1425 K.B. T.D. 3403 PBDT _____ Anhydrite Depth _____
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Received plugging orders from Steve Pfeifer on 04/21/04. Plugging began 10:15 am on 04/21/04.
Heavy mud in hole and between all plugs. Plugged with total of 135sx 60/40 Poz, 6% Gel.
Bottom plug @ 600' with 50 sx, 2nd plug @ 330' with 50 sx, top plug @ 40' with 10 sx and
plugged rathole with 15 sx, mousehole 10 sx. Plug down at 12:00 pm on 04/21/04.
Acid Services ticket #8509. SDC reported plugging to KCC (Steve Pfeifer) on 04/21/04.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Lanny Saloga/Gary Talbott Phone#: (620) 672-9508

Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 12:00 pm on 04/21/04. Plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 04/21/04 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Prothe 1-12

LOCATION: S/2 SE SW NW
API: 15-007-22818-0000

Section 12 T 33s R 12w
Barber County, Kansas

OWNER: Anderson Energy, Inc.
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 14-Apr-04
COMPLETED: 21-Apr-04

TOTAL DEPTH: **DRILLER** 3403 FEET
LOGGER Not Logged FEET

Ground Elevation: 1416
KB Elevation: 1425

LOG

0 -	3 FEET	Top Soil
3 -	180 FEET	Surface Sands and Clay
180 -	1750 FEET	Redbeds, Shales and Salt
1750 -	3403 FEET	Limestone, Shale and Dolomite

CASING RECORDS

Surface Casing-8-5/8"

Spud @ 5:15 pm on 04/14/04. Drilled 12-1/4" hole to 315'. Ran 7 joints of new 23# 8-5/8" surface casing, tally 298.68' set at 309.68' KB. Strapped bottom 3 joints, welded collars on other 4 joints. Cemented with 220 sx 60/40 Poz, 2% Gel, 3% CC and 1/4# celloflake per sx. Cement did circulate. Plug down @ 11:30 pm on 04/14/04. By Acid Services, ticket # 8283.

Plugging Data:

Received plugging orders from Steve Pfeifer on 04/21/04. Plugging began 10:15 am on 04/21/04. Heavy mud in hole and between all plugs. Plugged with total of 135sx 60/40 Poz, 6% Gel. Bottom plug @ 600' with 50 sx, 2nd plug @ 330' with 50 sx, top plug @ 40' with 10 sx and plugged rathole with 15 sx, mousehole 10 sx. Plug down at 12:00 pm on 04/21/04. Acid Services ticket #8509. SDC reported plugging to KCC (Steve Pfeifer) on 04/21/04.

DEVIATION SURVEYS

1/4 degree(s) at	315	feet
1/4 degree(s) at	1423	feet
1/4 degree(s) at	2294	feet
1-1/4 degree(s) at	3225	feet
1 degree(s) at	3398	feet

RECEIVED
APR 26 2004
KCC WICHITA