

2-1 15-153-20158-00-02

To: 6 041273
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 153-20,158A
C NW NW , SEC. 22 , T 1 S, R 32 W/Ex

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

4620 feet from S section line

4620 feet from E section line

Operator: John O. Farmer Inc.

Lease Name Kastens B Well # 4

Name & Address: Box 352

County Rawlins 135.68

Russell, Ks. 67665

Well Total Depth 4175 feet

Conductor Pipe: Size feet

Surface Casing: Size 85/8 feet 255 w/160

Abandoned Oil Well xx Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing License Number

Address Oberlin, Ks.

Company to plug at: Hour: 10:00AM Day: 1 Month: Year: 19

Plugging proposal received from Lawrence Slim Eichman

(company name) J. O. Farmer (phone)

were: 4 1/2 casing set at 4174 w/150 sks cement. Perfs at 3985 to 4087.

Ordered 300 sks 65/35 poz 10% gel w/1/2 lb f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 11:30 Day: 1 Month: Feb. Year: 19 91

ACTUAL PLUGGING REPORT Pumped in 4 casing w/225 sks cement w/1/2 lbs

f.c. and 5 sks hulls mixed in cement. Max 700 lbs. S.I. 350 lbs.

Pumped in 8 5/8 casing w/25 sks cement w/1/2 lb f.c. mixed in cement. Max 200 lbs. S.I. 200 lbs.

RECEIVED STATE CORPORATION COMMISSION

MAR 13 1991

3-13-1991 CONSERVATION DIVISION Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form) observe this plugging.

INVOICED
DATE 3-15-91
INV. NO. 31172

J.O.S.

Signed Dennis L. Hamel (TECHNICIAN) Dennis Hamel