

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD 15-153-20455-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Rawlins SEC. 21 TWP. 1 RGE. 32 NE
 Location as in quarters or footage from lines:
 C/NW/SE

Lease Owner John O. Farmer, Inc.
 Lease Name Reuber Well No. #4
 Office Address Box 352 - Russell, Kansas 67665
 Character of Well (Completed as Oil, Gas or Dry Hole): D & A
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced June 23, 1983
 Plugging completed June 28, 1983
 Reason for abandonment of well or producing formation Depleted

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4150'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	311'	NONE
				5 1/2"	4149'	1812.30'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.


Dumped five (5) sacks cement, sanded to 3935' and dumped five (5) sacks
 cement. Shot casing at 3100', 2500', 2000' and 1800'.
Pulled fifty (50) joints 5 1/2" casing.
Squeezed well with two (2) sacks hulls, eight (8) sacks gel,
 one hundred (100) sacks cement, thirty-two (32) sacks gel, released plug and
 pumped seventy (70) sacks 50/50 pozmix cement with 6% added gel and 3%
 calcium chloride.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

RECEIVED
 7-15-1983
JUL 15 1983
 (Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend,
 (Address) Ks. 67530

CONSERVATION DIVISION
 Wichita, Kansas
 SUBSCRIBED AND SWORN TO before me this 14th day of July, 1983



Margaret Prosser
 Notary Public.

My Commission expires: _____