

2-23

6 031337

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 150'
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 153-20,505-00-00
E C SW SW SEC. 22, T 1 S, R 32 (W/E)

660 feet from S section line
660 4470 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Reuber Well # 6

Operator: John O. Farmer Inc.

County Rawlins 134.55

Name & Address Box 352

Well Total Depth 4140 feet

Russell, Ks. 67665

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 300'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Eng. Inc. License Number _____

Address Great Bend, Ks. 67539

Company to plug at: Hour: AM Day: 23 Month: Feb Year: 19 90

Plugging proposal received from _____

(company name) Rockhold (phone) _____

were: 8 5/8" set at 300' w/225 sks. 4 1/2" set at 4139' w/150 sks. PBTD 4074'.

4 1/2" set at 4139' w/150 sks. Perf 3989' - 96'. Order sand and common cement.

Pull pipe. Order 250 sks 65/35poz 10% gel 2% dicel 500# hulls. Halliburton Cement

Co. Webb water trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:20AM Day: 23 Month: Feb Year: 19 90

ACTUAL PLUGGING REPORT Sand bottom to 3925' w/4 sks common cement on sand w/

bailer. Recovered 1540' of 4 1/2" casing. Shots at 1800' and 1540'.

Squeezed 8 5/8" w/250 sks cement blend w/500# hulls mixed into max psi

400#. Close in psi 150#. Plug complete.

3-15-1990
MAR 15 1990

Remarks: Additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-16-90

INV. NO. 27691

Gil S.

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow