

4-032086

9-6

API Number: 15-153-20,008-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NW NW NE /4 SEC. 07, 01S, 33 W
4950 feet from S section line
2200 feet from E section line

Operator license# 5552

Lease: Palmer Well # 1

Operator: Gore Oil Company

County: Rawlins

Address: P.O. Box 2747
Wichita, Kansas 67201

Well total depth 4190 136.18 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 209 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 6 Month: September Year: 1995

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone:

Were: Order 400 sxs 60/40 pozmix - 6% gel - 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1995

9-13-95

CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:15 P.M., Day: 6, Month: September, Year: 1995

Actual plugging report: 8 5/8" set at 209' cwc with 100 sxs. 5 1/2" set at 4190' with 775 sxs. Prod. Perfs at 3821' - 4113'. PBTD 4170'. 5 1/2" cwc from 4190' to surface. Squeezed 5 1/2" with 350 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 900#. Close in P.S.I. 400#. Tested 8 5/8" to 1000# P.S.I. cement at surface. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO

Plugged through TUBING, CASING. Elevation: GL

INVOICED

I did [X] / did not [] observe the plugging.

Carl Goodrow

(agent)

DATE OCT 04 1995

Form CP-2/3

INV. NO. 43642