

4-032088

9-6

-00-00

TO;  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-153-20,024

NE NE NW /4 SEC. 07, 01S, 33 W  
4840 feet from S section line  
3080 feet from E section line

Operator license# 5552

Lease: Cora Graves Well # 1

Operator: Gore Oil Company

County: Rawlins

Address: P.O. Box 2747  
Wichita, Kansas 67201

Well total depth 4470 <sup>145.28</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 3/4 Inch @ 237 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 6 Month: September Year: 1995

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone: \_\_\_\_\_

Were: Order 400 sxs 60/40 pozmix - 6% gel - 500# hulls.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 15 1995

CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 2:00 P.M., Day: 6, Month: September, Year: 1995

Actual plugging report: 8 5/8" set at 237' cwc with 225 sxs. 5 1/2" set at 4254' with 125 sxs. 5 1/2" squeezed with 150 sxs at 1735'. Prod. Perfs at 4057' - 4104'. PBTD 4104'. Squeezed 5 1/2" with 350 sxs cement blend with 500# hulls mixed into Max. P.S.I. 350#. Close in P.S.I. 0#. Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 300#. Close in P.S.I. 150#. Plug complete.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES \_\_\_\_\_ NO \_\_\_\_\_

Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES \_\_\_\_\_, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL

[ did  ] / did not [  ] observe the plugging.

**INVOICED**

DATE OCT 04 1995

INV. NO. 43639

Carl Goodrow  
(agent)

Form CP-2/3