

12-18

4-041553

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-153-20,034 ²⁰⁰⁰

N2 N2 NE /4 SEC. 07, 01 S, 33 W
4840 feet from S section line
1320 feet from E section line

Operator license# 5552

Lease Palmer well # 4

Operator: Gore Oil Company

County Rawlins

Address: P.O. Box 2757
Wichita, Kansas 67201

Well total depth 4170 feet ^{135.53}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 237 feet
w/160 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Oberlin, Kansas

Company to plug at: Hour: A.M. Day: 18 Month: December Year: 93

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone:

Were: 5 1/2" casing set @ 4194' w/550 sx. cement. Perf. @ 3832' -
4194'. W.L.M. 4150' - T.O.F. @ 2700'. Top squeeze hole @ 2250' -
Base Dakota.

Ordered 450 sx. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:40P.M., Day: 18, Month: December, Year: 93

Actual plugging report: Hooked-up to 8 5/8" S.P. Pumped in 100 sx. cement with 100# hulls. Max. 200#. S.I.P. 200#.

Hooked-up to 5 1/2" casing. Pumped in 350 sx. cement with 400# hulls. Max. 500#. S.I.P. 500#.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: GL

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
110
1-3-94

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION

JAN 03 1994

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 1-6-94

INV. NO. 39630