

4-041549

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-153-20,061 <sup>0000</sup>

E2 E2 SE /4 SEC. 07 , 01 S, 33 W  
1320 feet from S section line  
400 feet from E section line

Operator license# 5552

Lease Palmer well # 7

Operator: Gore Oil Company

County Rawlins

Address: P.O. Box 2757  
Wichita, Kansas 67201-2757

Well total depth 4170 feet <sup>135.53</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 270 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Halliburton Cementing License#    

Address: Oberlin, Kansas

Company to plug at: Hour: 8:30A.M. Day: 15 Month: December Year: 93

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone:    

Were: 5 1/2" casing set @ 4198' w/1275' sxs. cement. Perf. @ 3840' - 4124'. W.L.M. 4100' - T.O.F. @ 2700'. Hole squeezed from 1775' to T.D. Dakota cemented.

Ordered 450 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[     ], Part[ X ], None[     ]

Completed: Hour: 9:25A.M., Day: 15, Month: December, Year: 93

Actual plugging report: Hooked-up to 5 1/2" casing. Pumped in 350 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Max. 300#. S.I.P. 50#. Hooked-up to 8 5/8" S.P. Pumped in 100 sxs. 60/40 pozmix - 10% gel - 1/4# F.C. Max. 300#. S.I.P. 200#.

Remarks:

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO    

Bottom plug(in place): YES    , CALC    , NO     Dakota plug: YES X, NO    

Plugged through TUBING    , CASING X. Elevation:     GL    

RECEIVED  
STATE CORPORATION COMMISSION

DEC 21 1993

CONSERVATION DIVISION  
Wichita, Kansas

I did [ X ] observe the plugging.

Dennis L. Hamel

(agent) 12-21-93

DATE 12-29-93

INV. NO. 39585