

4-041551

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-153-20,068 ⁰⁰⁻⁰⁰

C NE /4 SEC. 07, 01 S, 33 W
3960 feet from S section line
1320 feet from E section line

Operator license# 5552

Lease Palmer well # 8

Operator: Gore Oil Company

County Rawlins

Address: P.O. Box 2757
Wichita, Kansas 67201-2757

Well total depth 4195 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 260 feet
w/200 sxs.

136.34

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Oberlin, Kansas

Company to plug at: Hour: 8:30A.M. Day: 15 Month: December Year: 93

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone:

Were: 5 1/2" casing set @ 4219' w/ 925' sxs. cement. Perf. @ 3840' - 4128'. W.L.M. 4100' - T.O.F. @ 2820'. Top casing squeezed at 1110' with base Dakota prior squeezed.
Ordered 450 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 1:30P.M., Day: 15, Month: December, Year: 93

Actual plugging report: Hooked-up to 5 1/2" casing. Pumped in 350 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls. Max. 550#. S.I.P. 500#. Hooked-up to 8 5/8" S.P. Pumped in 100 sxs. 60/40 pozmix - 10 % gel - 1/4# F.C. Max. 300#. S.I.P. 150#.

Remarks: Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X did not observe the plugging.

INVOICED

DATE 12-29-93

INV. NO. 39584

Dennis L. Hamel
HD. (agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1993
CONSERVATION DIVISION
Wichita, Kansas