

6 050142

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 153-20,571 00-00  
SW SE, SEC. 7, T. 1 S, R. 33 W XX  
660 feet from SE section line  
1980 feet from SE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6499

Lease Name Vap Well # 1

Operator: Abraxas Petroleum Corp.

County Rawlins

Name & Address P.O. BOX 17485

Well Total Depth 4240 137.80 feet

San Antonio, Tx. 78217

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 6033

Address 305 N. Water, Wichita, Ks.

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: October Year: 19 84

Plugging proposal received from Larry Wagner

(company name) Murfin Drilling Company (phone) \_\_\_\_\_

were: Order 195 lbs. 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel, 1 sk hulls and 8 5/8" plug. Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 1:30 PM Day: 19th Month: October Year: 19 84

ACTUAL PLUGGING REPORT

- 1st plug @ 2900 w/25 sks
- 2nd plug @ 2200 w/110 sks 1 sk flo-cel
- 3rd plug @ 360 w/40 sks
- 4th plug @ 40 w/8 5/8" 1 sk hulls and 10 sks cmt
- 10 sks in Rat Hole

Remarks: Cemented by Sun

STATE CORPORATION COMMISSION  
OCT 29 1984  
10-29-84

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE 10-30-84

Signed Arthur P. Leiker (TECHNICIAN) 10-26-84

INV. NO. 4529

10-19 NOV 19 1984