

4-032283

8-21

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-153-20,074-00-00

C N2 N2 NW /4 SEC. 08, 01, 33 W  
4950 feet from S section line  
3960 feet from E section line

R.L. Herbek  
#31274

Operator license# 31664

Lease: Palmer Well # C-4

Operator: Northwest Well Service

County: Rawlins 137.15

Address: 17509 County Road - #14  
Fort Morgan, CO 80701

Well total depth 4220 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 255 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Company Tools License# 31664

Address: 17509 County Road #14 - Fort Morgan, CO 80701

Company to plug at: Hour: P.M. Day: 21 Month: August Year: 1997

Plugging proposal received from: Randy

Company: Northwest Well Service Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.  
Order B.P. and common cement.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ ], Part [ X ], None [ ]

Completed: Hour: 12:30 P.M., Day: 21 Month: August, Year: 1997

Actual plugging report: 8 5/8" set at 255' w/200 sxs cwc. 4 1/2" set at 4220' with 250 sxs  
Prod. Perfs at 3847' - 3857'. Set B.P. at 3790' w/25 sxs common cement on plug. Shots at  
2200' - 1500'. Recovered 700' of 4 1/2" casing. Squeezed 8 5/8" with 140 sxs cement blend  
with 300# hulls. Mixed into Max. P.S.I. 200#. Held. Plug complete.

STATE CORPORATION COMMISSION  
1-1-98  
JAN 7 1998

Remarks:  
Condition of casing(in hole): GOOD BAD Any plug: YES  NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES  NO  
Plugged through TUBING, CASING Elevation: GL

I [ ] observe the plugging.

INVOICED  
JAN 08 1998

DATE

INV. NO. 49889  
8-21 JAN 29 1998

Carl Goodrow  
(agent)