



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1967
2-3-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Wichita Plaza, Wichita, Kansas.

Lease Name: Walsh Well No. 1

Location: GNE-NE Sec 22 Twp. 1 Rge. (E) (W) 32

County Rawlins Total Depth 4160 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

303'--8 5/8" Surface pipe, cement circulated with 200 Sx.

Circulate hole with heavy mud, set plug @ 660' and 20 Sx. cement.

" " 300' with 1/4 sk. hulls & 20 Sx. cement.

" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

Conservation Division Agent