

State of Kansas



15-153-20039-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

**VERBAL PERMIT FORM**  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 30 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 12-30-1968

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Sam G. Harrison, Trustee,

Complete Address: 2400 Bank of the Southwest Bldg., Houston, Texas.

Lease Name: Wicke Well No. 2

Location: App.-CSE-SW Sec. 21 Twp. 1 Rge. (E)(W) 32

County: Rawlins Total Depth 4160 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Favinger was instructed to plug the well as follows:

352'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1250'.

Circulate hole with heavy mud. Pull DP to 1500' and displace 100 Sx.  
cement thru DP. Pull DP to 365' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*M. S. Nichols*  
 Conservation Division Agent