

15-153-20158-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

*W* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 14 1973  
6-14-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Incorporated,

Complete Address Box #152, Russell, Kansas.

Lease Name Kastens Well No. 1

Location CNW-NW Sec. 22 Twp. 1 Rge. (E) (W) 32

County Rawlins Total Depth 4175'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 1:00PM Day 11 Month 6 Year 1973

The above well was plugged as follows:

255'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 1800'.

Circulated hole with heavy mud. Pulled DP to 2025' and displaced 110 Cu. Ft. cement  
thru DP from 2025' to 1700'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*  
Well Plugging Supervisor

INVOICED  
DATE 6/14/73  
INV. NO. 9508-W