

QR

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20039-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

12-30-1968
RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sam G. Harrison, Trustee,

Complete Address: 2400 Bank of the Southwest Building, Houston, Texas. 77002

Lease Name Wicke Well No. 2

Location App.-GSE-SW Sec. 21 Twp. 1 Rge. (E) (W) 32

County Rawlins Total Depth 4160'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Murfin Drilling Company,

Address: 617 Union Center Building, Wichita, Kansas. License No. _____

Operation Completed: Hour 2:00 PM Day 27 Month 12 Year 1968

The Above well was plugged as follows:

352' -- 8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1250'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 100 Sx. cement thru
DP from 1500' to 1175'. Pulled DP to 365' and displaced 25 Sx. cement thru DP from
365' to 290'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 12-30-68
INV. NO. 9121-W