

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-153-20003-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1967
2-3-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Walsh Well No. 1

Location CNE-NE Sec. 22 Twp. 1 Rge. (E) (W) 32

County Rawlins Total Depth 4160

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box # 486, Great Bend, Kansas. License No.

Operation Completed: Hour 8:00PM Day 27 Month 1 Year 1967

The Above well was plugged as follows:

303'--8 5/8" Surface pipe, cement circulated with 200 Sx.

Circulated hole with heavy mud, set plug @ 660' and displaced 20 Sx.

cement thru DP. Heavy mud to 300', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 2/3/67
INV. NO. 4711-W