

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-153-20677-00-01

API NUMBER 15-153-20677A

LEASE NAME Peterson

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2970 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 8 TWP. 1S RGE. 33 (X) or (W)

LEASE OPERATOR Allied Oil Company, Inc.

COUNTY Rawlins

ADDRESS HC3 Box 45A, Taneyville, MO 65759

Date Well Completed 12-87

PHONE# (417) 546-5885 OPERATORS LICENSE NO. 9325

Plugging Commenced 4-13-93

Character of Well Oil Non-commercial

Plugging Completed 4-13-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-29-93 (date)

by Carl Goodrow recommended and supervised procedure (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation L. K. C. Depth to Top 3928 Bottom 4198 T.D. 4279

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>L. K. C.</u>	<u>oil</u>	<u>4029</u>	<u>34'</u>	<u>8 5/8"</u>	<u>296'</u>	<u>none</u>
<u>"</u>	<u>"</u>	<u>4125.5</u>	<u>30.5</u>	<u>5 1/2"</u>	<u>4279'</u>	<u>none</u>
<u>Kiowa</u>	<u>water</u>	<u>2095</u>	<u>2165</u>	<u>perforate 5 1/2" w/</u>	<u>hole at 2135'</u>	

Describe in detail the method by which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

No casing recovered; perforated 5 1/2" casing in the Kiowa formation, pumped 250 sxs HOWCO HL cement w/4% added Gel and 500 lbs. cotton seed hulls to fill 5 1/2" casing; Pump 100sxs HL cement w/4% Gel added thru 8 5/8" Braden head between 5 1/2" & 8 5/8" esp. both finished with pressure.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address Oberlin, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Roy Grant

4-28-93

STATE OF Missouri COUNTY OF Taney, ss.

RECEIVED
STATE CORPORATION COMMISSION

Roy Grant (Employee of Operator) (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well filed that the same are true and correct, so help me God.

APR 28 1993

(Signature) Roy Grant

ARLENE TAYLOR Notary Public
Taney County State of Missouri
My Commission Expires July 26, 1995

(Address) HC3, Box 45A Taneyville, MO

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 1993

Arlene Taylor
Notary Public

My Commission Expires: July 26 1995