

API NUMBER 15-153-20704-00-00

LEASE NAME Vap "C"

WELL NUMBER 1

2310 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 8 TWP. 1S RGE. 33 (X) or (W)

COUNTY Rawlins

Date Well Completed 3-2-88

Plugging Commenced 10-16-95

Plugging Completed 10-16-95

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Allied Oil Company, Inc.

ADDRESS 3878 Hulls Ford Rd., Taneyville, MO 65759

PHONE# (417) 546-5885 OPERATORS LICENSE NO. 9325

Character of Well Non commercial oil well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-10-95 (date)

by Carl Goodrow recommended and supervised procedure (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation LKC Depth to Top 3938' Bottom 4189' T.D. 4230'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From  | To                                 | Size   | Put In | Pulled out |
|-----------|---------|-------|------------------------------------|--------|--------|------------|
| LKC       | oil     | 4032' | 36'                                | 8 5/8  | 316'   | None       |
| LKC       | oil     | 4127' | 31'                                | 4 1/2" | 4225'  | None       |
| Kiowa     | water   | 2135' | 2 shots as directed by Mr. Goodrow |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 0 feet to 4190 feet each set.

Perf. w/2 holes @2135'; 50 sxs into surf. casing, 300 PST, pump and fill 4 1/2

csg. with 225 sxs & 500# hulls Shut in pressure 100PSI; No casing recovered.

Total cement used 275 sxs 60-40 POZ, with 6% Gel, under direct supervision of KCC Representative Carl Goodrow.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc License None required

Address P. O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Allied Oil Company, Inc. NOV - 2 1995

STATE OF Mo. COUNTY OF Taney, ss. 11-2-95

Roy A. Grant

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Roy A. Grant

(Address) 3878 HULLS FORD RD. TANEVILLE, MO

SUBSCRIBED AND SWORN TO before me this 30th day of October, 19 95

Kathy Fleetwood  
 Kathy Fleetwood Notary Public

My Commission Expires: February 3, 1997