

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

~~15-153-19000-0000~~
 API NUMBER 15-153-0521500-00

LEASE NAME Wilhelm Unit

WELL NUMBER 9

1980 Ft. from S Section Line

1956 Ft. from E Section Line

SEC. 20 TWP. 1S RGE. 32 (E) or (W)

COUNTY Rawlins

Date Well Completed 4/9/60

Plugging Commenced 8/14/97 5:00pm

Plugging Completed 8/15/97 12:00pm

KANSAS CORP. TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

~~10-3-1997~~ 10-3-1997

LEASE OPERATOR Philpott Oil & Gas Co., Inc.

ADDRESS P.O. Box 450 Atwood, Ks 67730

PHONE#(913) 626-3011 OPERATORS LICENSE NO. 3602

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/14/97 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation LKC Depth to Top 3965 Bottom 4107 T.D. 4204

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		GL	371	8 5/8	371	0
		GL	4204	5 1/2	4204	1184

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Shot casing off at 1184'. Pulled and laid down 10 joints. Mixed 130 sacks 60/40 poz w/10% gell. Pumped down casing and plugged at 900 ft. Pulled and laid down casing. Mixed 60 sacks 60/40 poz w/10% gell and 2 sacks hulls. Pumped down casing. Cement circulated to cellar. Pulled and laid down rest of casing. Filled cellar with cement.
 (If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Northwest Well Service License No. 31664

Address 17509 Road 14, Ft. Morgan, Co 80201

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Philpott Oil & Gas Co., Inc.

STATE OF Kansas COUNTY OF Rawlins, ss.

Roger W. Philpott, President (Employee of Operator) or (Operator) or above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.



(Signature) [Signature]

(Address) P.O. Box 450 Atwood, Ks 67730

SUBSCRIBED AND SWORN TO before me this 29th day of Sept, 19 97

J. L. Dixon
 Notary Public

My Commission Expires: 10-23-98