

8-15

4-032249

15-153-05215-80 00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-~~15319000-00-00~~

NW SE \_\_\_\_\_ / 4 SEC. 20, 01, 32 W  
1980 feet from S section line  
1956 feet from E section line

Operator license# 3602

Lease: Wilhelm Unit Well # 9

Operator: Philpott Oil & Gas

County: Rawlins 136.63

Address: P.O. Box 450  
Atwood, Kansas 67730

Well total depth 4204 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 371 feet  
W/300 sxs.

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cement Company License# \_\_\_\_\_

Address: Russell Kansas 67665

Company to plug at: Hour: P.M. Day: 14 Month: August Year: 1997

Plugging proposal received from: Roger Philpott

Company: Philpott Oil & Gas Phone: 9-15-1997

Were: Order 200 sxs 60/40 pozmix - 10% gel - 300# hulls.  
CIBP at 2710'.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 12:00 P.M., Day: 15 Month: August, Year: 1997

Actual plugging report: 8 5/8" set at 371' w/300 sxs cwc. 5 1/2" set at 4204' with 250 sxs. Prod. Perf. At 3965' - 4113'. Shot at 2200' - 1600' - 1184' recovered. Mixed and pumped 130 sxs cement blend with 200# hulls. Pulled to 375' - circulated cement blend with 60 sxs. Pulled casing. Hole full. Plug complete.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL

I did [ X ] / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

Form CP-2/3

**INVOICED**

DATE 9-16-97

INV. NO. 49020

8-15