

8-14

4-032253

E-17,400

API Number: 15-153-20,245-0001

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

C SE SW / 4 SEC. 20, 01, 32 W
660 feet from S section line
3300 feet from E section line

Operator license# 3602

Lease: Wilhelm Unit Well # 19

Operator: Philpott Oil & Gas

County: Rawlins 135.85

Address: P.O. Box 450
Atwood, Kansas 67730

Well total depth 4180 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 372 feet
W/250 sxs.

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell Kansas 67665

Company to plug at: Hour: A.M. Day: 14 Month: August Year: 1997

Plugging proposal received from: Roger Philpott

Company: Philpott Oil & Gas Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 300# hulls.

9-15-1997

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:30 A.M., Day: 14 Month: August Year: 1997

Actual plugging report: 8 5/8" set at 372' w/250 sxs cwc. 5 1/2" set at 4180' with 200 sxs. Prod. Perf. At 3970' - 4121'. Shot at 2200' - 1600'. Recovered 1200' of 5 1/2". CIBP at 3900' w/ 4 sxs cement. Squeezed with 200 sxs cement blend with 300# hulls mixed into Max. P.S.I. 300#. Held. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

10

Form CP-2/3

INVOICED

DATE 9-16-97

INV. NO. 49021

8-14