

Oxford Exploration Company

1030 DENVER CLUB BUILDING
DENVER, COLO. 80202
(303) 572-3821

October 19, 1977

State Corporation Commission
Conservation Division
245 North Water
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
10-21-1977
OCT 21 1977
CONSERVATION DIVISION
Wichita, Kansas

Gentlemen:

15-153-20302-00-00

We are in receipt of your invoice for a plugging assesment on our #1 Pettera well, located SW/4 NE/4, section 3, T1S-R31W, Rawlins County, Kansas. After Rains and Williamson requested plugging orders on our behalf for the well, we decided to attempt completion and ran 4469 feet of 4 1/2", 10.5# casing cemented with 250 sacks. We are presently waiting on the availability of a completion unit to attempt completion.

We will forward a completion form at such time as we have completed the well. In the event we should decide to abandon the well after attempting completion we will request plugging orders from your Mr. Balthazor. We are sending a set of samples to the Kansas Geological Survey this week.

Please advise us whether we are required to supply any additional information.

Yours very truly,



David E. Park, Jr.

DEP/em

cc: Rains and Williamson

DRILLER'S LOG

15-153-20302-00-00

COMPANY: Oxford Exploration Co., Inc.

SEC. 3 T. 1S R. 31W

WELL NAME: #1 Petera

LOC. C SW NE

COUNTY: Rawlins

RIG NO. #4

TOTAL DEPTH 4577'

ELEVATION

COMMENCED: 9-27-77

COMPLETED: 10-8-77

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 346' w/175 sx. 60/40 poz., 2% gel, 3% cc.

PRODUCTION: 4 1/2" @ 4469' w/250 sx. 50/50 poz., 3% CFR2, 1000gal. mud flush ahead of cement.

LOG

(Figures Indicate Bottom of Formations)

Shale	1015
Shale & Sand	2050
Sand, Shale & Sand	2300
Shale & Sand	2460
Shale & Redbed	3080
Redbed & Shale	3310
Lime & Shale	3455
Shale & Lime	3623
Lime & Shale	3730
Lime	4150
Lime & Shale	4230
Lime	4577
<u>ROTARY TOTAL DEPTH</u>	<u>4577</u>

RECEIVED
 STATE CORPORATION COMMISSION
 10-21
 OCT 21 1977
 10-21-1977
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Petera well.

Wilson Rains
 Wilson Rains

Subscribed and sworn to before me this 12 day of October, 1977.

My Appointment Expires:
10-4-79

Juanita M. Green
 Juanita M. Green

