



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 23 1973  
CONSERVATION DIVISION  
Wichita, Kansas

10-23-73

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drilling Co., Inc., has this  
date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Inc., & Bill J. Porter,

Complete Address: 950 Century Plaza, Wichita, Kansas.

Lease Name: Bucy Well No. 1

Location: SE-NW Sec. 9 Twp. 1 Rge. (E)(W) 33

County: Rawlins Total Depth 4150' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

255'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 1800'.

Circulate hole with heavy mud. Pull DP to 2025' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

W. J. Nichols  
Conservation Division Agent