

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 129-20246-00-02 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 10/03/1976.

Well Operator: Colorado Interstate Gas Company KCC License #: 7117  
(Owner / Company Name) (Operator's)

Address: P. O. Box 1087 City: Colorado Springs

State: CO Zip Code: 80944 Contact Phone: ( 719 ) 520 - 4557

Lease: Boehm Well #: 30 Sec. 10 Twp. 33 S. R. 42  East  West

NE - SE - \_\_\_\_\_ Spot Location / QQQQ County: Morton

2,410 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

132 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: Gas Storage Well

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 13-3/8"-8-5/8" Set at: 1,370' GL Cemented with: 700 Sacks

Production Casing Size: 5-1/2" Set at: 4,944' GL Cemented with: 1,025 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs: 1,413'-23', 1,436'-46', 1,850'-60', 4,771'-84', 4,824'-56'. CIBP @ 4,814'.

Elevation: 3,461' ( G.L. /  K.B.) T.D.: 4,952' P.B.T.D.: 4,102' Anhydrite Depth: 1,362' GL  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): (See Attachment)

**RECEIVED**

**MAY 03 2004**

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

**KCC WICHITA**

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: David Veatch

Phone: ( 970 ) 376 - 1273

Address: P. O. Box 615 City / State: Fort Morgan, CO 80723

Plugging Contractor: Key Energy Services, Inc. KCC License #: 33223  
(Company Name) (Contractor's)

Address: P. O. Box 1383, Guyman, OK 73942 / 3801 Valley Park Dr. Phone: ( 580 ) 338 - 0664  
EL RENO, OK 73036

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4/30/04 Authorized Operator / Agent: David Veatch  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

8/04

4/04

Well Tech Mid-Continent, Inc. dba

**Boehm 30**

Preliminary procedure confirmed w/ KCC, Steve Durrant 03/12/04

Run tubing open ended to 2000'

Spot hulls and cement across perfs and holes from 1860' to 1413'

Pull 2-7/8" tubing

WOC

Run tubing and tag TOC to verify; repeat cementing if necessary

Lay down tubing

Spot 10 sx cement plug at surface

Cut off casing and weld cap

Fill surface casing annulus with cement

Pressure test surface casing annulus to 500 psig

**RECEIVED**  
**MAY 03 2004**  
**KCC WICHITA**

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor   Brian J. Moline, Chair   John Wine, Commissioner   Robert E. Krehbiel, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Colorado Interstate Gas Company  
PO Box 1087  
Colorado Springs, CO 80944

May 06, 2004

Re: BOEHM #30  
API 15-129-20246-00-02  
NENESE 10-33S-42W, 2410 FSL 132 FEL  
MORTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely

  
David P. Williams  
Production Supervisor