

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15 - 129-10266 - 00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 01/26/1951.

Well Operator: Colorado Interstate Gas Company KCC License #: 7117
(Owner / Company Name) (Operator's)

Address: P. O. Box 1087 City: Colorado Springs

State: Colorado Zip Code: 80944 Contact Phone: (719) 520 - 4557

Lease: Boehm Well #: 1 Sec. 14 Twp. 33 S. R. 42 East West

NE - NE - NW Spot Location / QQQQ County: Morton

4,950 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

3,030 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: Gas Storage Well

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 13" Set at: 260' GL Cemented with: 250 Sacks

Production Casing Size: 5-1/2" Set at: 5,030' GL Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs: 4,784-96(Sqzd.), 4,842-68(Open), 4,876-82(Sqzd.), 4,892-96(Sqzd.), 4,922-26(Sqzd.)
CIBP @ 4,872'. All depths GL.

Elevation: 3,485' (G.L. / K.B.) T.D.: 5,987' PBTD: 4,872' Anhydrite Depth: 1,396'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed):
See Attachment.

**RECEIVED
MAY 03 2004
KCC WICHITA**

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: David Veatch

Phone: (970) 376 - 1273

Address: P. O. Box 615 City / State: Fort Morgan, CO 80723

Plugging Contractor: Well Tech Mid Continent Inc., dba Key Energy Services, Inc. KCC License #: 33223
(Company Name) (Contractor's)

Address: P. O. Box 1383, Guyman, OK 73942 / 3801 Valley Park Dr. El Reno, OK 73036 Phone: (580) 338 - 0664

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 4/30/04 Authorized Operator / Agent: [Signature]
(Signature)

Boehm 1

Preliminary procedure confirmed w/ KCC, Steve Durrant 03/12/04

Dig out around wellhead to expose 13" x 8-5/8" casing interface. If there are outlets then rig to circ., otherwise fill back in.

Pump 300# hulls + 40 sk cmt to bottom

Use 36 viscosity, 9# mud between plugs in open-hole sections

Free-point 5-1/2" casing and cut off at _____ ft

Spot 50 sk plug on stub at _____ ft

Pull casing to 2711'

Pump 50 sk plug at 2711'

Lay down 5-1/2" casing

Free-point 8-5/8" casing and cut off at _____ ft

Lay down 8-5/8" casing

Run tubing to 8-5/8" casing stub

Spot 50 sk plug on stub at _____ ft

Pull tubing to _____ ft

Spot _____ sk plug from _____ ft to _____ ft

Pull tubing to 25 ft

Spot 25 ft plug from 25 ft to surface

Cut off 13" casing 5' below grade and weld on cap.

RECEIVED
MAY 03 2004
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Colorado Interstate Gas Company
PO Box 1087
Colorado Springs, CO 80944

May 06, 2004

Re: BOEHM #1
API 15-129-10266-00-01
NENENW 14-33S-42W, 4950 FSL 3030 FEL
MORTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely


David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888