

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22774-00-00
Spot: NWNENE Sec/Twnshp/Rge: 27-11S-16W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: BOWLBY Well #: 1-27
County: ELLIS Total Vertical Depth: 3355 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

PROD Size: 4.5 feet: 3359 w/200 sxs cmt
SURF Size: 8.625 feet: 900 w/370 sxs cmt

\$10904

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/14/2004 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Order 300 sxs cement and 600# hulls.
Perf at 1500' - 950' - 475'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2004 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Ran tubing to 2620' - spotted 70 sxs cement with 300# hulls.
Pulled tubing to 1350' - circulated with 70 sxs cement with 300# hulls.
Pulled all tubing - squeezed 4 1/2" casing with 160 sxs cement
(circulated cement thru casing and out thru 8 5/8" annulus) to 600# - blew hole in casing.
Cement held at top of casing.
Total of 300 sxs 60/40 pozmix - 10% gel and 600# hulls.

RECEIVED
MAY 03 2004
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS BOWLBY C-1. SWIFT SERVICES, INC. EVANS TANK-WATER.

Plugged through: TBG

District: 04

Signed

Roger Moses

(TECHNICIAN)

100-
INVOICED

5-5-04

2004061484

Form CP-2/3

APR 28 2004

EXLE

MAOIDEF

REPLACEMENT CARD

TEXOKKA DRILLING, INC.
2705 VINE STREET
HAYS, KS. 67601

#1 'C' BOWLBY

27-11-16W
NW NE NE


CONTR EMPHASIS OIL OPERATIONS CTY FILLIS

GEOL _____ FIELD CHRISLER EAST

ELV 1739 KB SPD 12/21/81 CARD ISSUED 8/12/82 IP P 2 BOPD & WTR

API 15-051-22,774

SHAW(TOP) - INTV NA
LKC - INTV NA



LOG	Tops	Depth/Datum
ANH	894+	845
B/ANH	928+	811
TOP	2660-	921
HEEB	2904-	1165
TOR	2925-	1186
LANS	2952-	1213
BKC	3194-	1455
ARB	3330-	1591
RTD<D	3355-	1616

E 8 5/8 " 900, PROD CSG NA
NO CORES OR DSTS RPTD
MICT - CO, PF (CONG) INTV NA, SWB DWN, SLI SO, NON-COM-
MERCIAL, SET BP (DEPTH NA), PF (MARM) INTV NA, SWB DWN,
SLI SO, NON-COMMERCIAL, SET BP (DEPTH NA), PF (LKC) INTV
NA, SWB DWN, SO, PF (TOP) INTV NA, SWB DWN, SO, POP, P 2
BOPD & WTR, COMMINGLED - NO OTHER INFO TO BE RELEASED
BY OPERATOR

INFO RELEASED: 10/30/86 - ADDED WELL INFO
NOTE: ORIGINALLY FIRST REPORTED AS #2 BOWLBY, INFO RE-
LEASED: 7/7/83 - WAS TIGHT HOLE

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS