

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-185-33287-00-00

API NUMBER Comp. 4-12-60

LEASE NAME Satterlee

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

2970 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 36 TWP. 24 RGE. 15W (E) or (W)

COUNTY Stafford

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd. North, Bldg.300, Wichita, Ks. 67228

PHONE#(316) 682-1537 OPERATORS LICENSE NO. 5030

Date Well Completed _____

Character of Well Oil

Plugging Commenced 4-14-04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-15-04

The plugging proposal was approved on _____ (date)

By Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4476'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Sand</u>				<u>8-5/8"</u>	<u>280'</u>	<u>None</u>
<u>Mud</u>				<u>5-5/8"</u>	<u>4476'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand to 4350' and 5 sacks cement. Perforated casing @960 ft. Ran 960' of 2-3/8" tubing, pumped 110 sacks 60/40 pos, 6% gel and circulated to surface. Layed down tubing, tied onto 5-5/8" casing and pumped 80 sacks cement and circulated to surface on the backside. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED

SUBSCRIBED AND SWORN TO before me this 27th day of April, 2004

APR 30 2004

My Commission Expires:

KCC WICHITA

