

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-20575-00-00

LEASE NAME William Mast #B-2

WELL NUMBER #B-2

1775 Ft. from <sup>N</sup> Section Line

2540 Ft. from <sup>W</sup> Section Line

SEC. 24 TWP. 31 RGE. 36 (E) or (W)

COUNTY Stevens

Date Well Completed 7/82 ~~7-28/1982~~

Plugging Commenced 4/12/04

Plugging Completed 4/15/04

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR ExxonMobil Oil Corp.

ADDRESS P.O. Box 4358 Houston, TX 77210

PHONE# (281) 654-1934 OPERATORS LICENSE NO. 5208

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/05/04 (date)

by David P. Williams Production Supervisor (KCC District Agent's Name).

Is AGO-1 filed? YES If not, is well log attached? No

Producing Formation PANOMA Depth to Top 2897 Bottom 2963 T.O. 3090

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Council Grove</u>		<u>2897</u>	<u>2963</u>			<u>NONE</u>
<u>Sand</u>			<u>623</u>	<u>8.625</u>	<u>623</u>	<u>⊖</u>
<u>Prod</u>		<u>3090</u>	<u>515</u>		<u>3090</u>	<u>⊖</u>

RECEIVED  
KANSAS CORPORATION COMMISSION  
05-06-2004  
MAY 06 2004  
CONSERVATION DIVISION  
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character, of same and depth placed, from feet to feet each set  
PUMP 400 # HULLS & 25 SKS CMT THUR 2<sup>3</sup> BTBG. TO PLUG PERFS. DISPLACE W/ 1 BBL. MUD. TRG. ON VACUUM. P.O.H. W/ 20.75. 2<sup>3</sup> BTBG. & CIRCULATE HOLE W/ MUD. HOLE CIRCULATED. P.O.H. W/ TBG. & LAYDOWN. 4/14/04 PULL STRETCH ON 5.5. NO STRETCH. F/L INSIDE 5.5. 1380' TO C @ 2840' DUMA (25 SKS CMT ON TOP OF FLUID C. 1380' SOON. 4/15/04 TAG CMT AT 1215' FLUID AT 1150' PUMP 12 BBL. MUD TO 650' PUMP 10 SKS CMT DOWN 5.5. FILL TO SURFACE. PUMP 5 SKS CMT ON BACKSIDE; fill to SURFACE.

Name of Plugging Contractor SARGENT AND HORDON PLUGGING INC. License No. 31151

Address Rt 1, Box 49BA TYRONE, OK 73951

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EXXONMOBIL OIL CORP.


STATE OF TEXAS COUNTY OF \_\_\_\_\_, ss.

GREGORY L ZERR Gregory J. Zerr (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gregory J. Zerr  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 21st day of April, 19 2004

Sherry Annis  
Notary Public



USE ONLY ONE SIDE OF EACH FORM

Bm

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20575-00-00  
Spot: NESENW Sec/Twnshp/Rge: 24-31S-36W  
1775 feet from N Section Line, 2540 feet from W Section Line  
Lease Name: WILLIAM MAST Well #: B-2  
County: STEVENS Total Vertical Depth: 3090 feet

Operator License No.: 5208  
Op Name: LXXONMOBIL OIL CORP  
Address: 14950 HEATHROW FORREST PARKWA  
HOUSTON, TX 77210

PROD Size: 5.5 feet: 3090 650 SX CMT  
SURF Size: 8.625 feet: 623 300 SX CMT

Well Type: GAS UIC Docket No: Date/Time to Plug: 04/13/2004 1:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 25 SX CMT & 400# HULLS. PLUG AT 650' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

*Copy*

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/15/2004 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 3060'. CASING LEAK @ 2820'. PUMP 400# HULLS & 25 SX CMT THROUGH 2 3/8" TUBING TO PLUG PERFS. DISPLACE WITH 9 BBL MUD. TUBING ON VACUUM. PULL OUT OF HOLE WITH 20 JOINTS 2 3/8" TUBING & CIRCULATE HOLE WITH MUD. HOLE CIRCULATED. PULL OUT OF HOLE WITH 2 3/8" TUBING & LAY DOWN. 04/14/04: PULL STRETCH ON 5 1/2". NO STRETCH. FLUID LEVEL INSIDE 5 1/2" @ 1380'. TOC @ 2840'. DUMP 12 SX CMT ON TOP OF FLUID @ 1380'. SDON. 04/15/04: TAG CMT AT 1215'. FLUID AT 1150'. PUMP 12 BBL MUD TO 650'. PUMP 70 SX CMT DOWN 5 1/2". FILL TO SURFACE. PUMP 5 SX CMT ON BACKSIDE, FILL TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2924	2963		
2897	2911		

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 06 2004  
CONSERVATION DIVISION  
WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

*Jim Holland*  
PORT #  
(TECHNICIAN)