

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-20342-00-00

LEASE NAME MARTHA REYNOLDS B-#

WELL NUMBER B-2

1500 Ft. from N Section Line

1300 Ft. from W Section Line

SEC. 20 TWP. 31S RGE. 36 (E) or (W)

COUNTY STEVENS

Date Well Completed 6/6/77/1977

Plugging Commenced 4/07/04

Plugging Completed 4/12/04

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR EXXON MOBIL OIL CORP.

ADDRESS P.O. Box 4358 Houston, TX 77210

PHONE (281) 654-1934 OPERATORS LICENSE NO. 5208

Character of Well Gas

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/05/04 (date)

by DAVID P. WILLIAMS (Production Supervisor) (KCC District Agent's Name).

Is ACC-1 filed? YES If not, is well log attached? No

Producing Formation PANOMA Depth to Top 2883 Bottom 2910 T.D. 2995

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out	RECEIVED KANSAS CORPORATION COMMISSION 05-06-04 MAY 06 2004
<u>COUNCIL GROVE / Run</u>	<u>Gas</u>	<u>2883</u>	<u>2910</u>	<u>5.5</u>	<u>2995</u>	<u>104'</u>	
<u>SWP</u>			<u>Cell</u>	<u>8.625</u>	<u>Cell</u>	<u>0</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
PBTD 2970' WELL SANDED IN AT 1333'. 1st PLUG LOAD HOLE WITH MUD. SPOT 25 SX CNT AT 1007' THUR TO D. 2nd PLUG-PULL TO 650' AND SPOT 50 SX CNT. 3rd PLUG PULL TO 40' AND SPOT 10 SX CNT. STAYED FULL.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address Route 1, Box 490A TYRONE, OK. 73951-9131

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EXXON MOBIL OIL CORP.

STATE OF TEXAS COUNTY OF \_\_\_\_\_, ss.

GREGORY L. ZERR Gregory L. Zerr (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Gregory L. Zerr

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 21st day of April, 19 2004

Sherry Annis  
Notary Public

NOTARY PUBLIC - State of Kansas  
5-12 SHERIDAN  
My Appt. Exp. \_\_\_\_\_

My Commission Expires: \_\_\_\_\_  
USE ONLY ONE SIDE OF EACH FORM

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20342-00-00  
Spot: NW Sec/Twshp/Rge: 20-31S-36W  
1500 feet from N Section Line, 1300 feet from W Section Line  
Lease Name: MARTHA REYNOLDS B Well #: 2  
County: STEVENS Total Vertical Depth: 2995 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: 14950 HEATHROW FORREST PARKWA  
HOUSTON, TX 77210

CIBP Size: feet: 2830  
PROD Size: 5.5 feet: 2995 WITH 300 SX CMT  
SURF Size: 8.625 feet: 611 WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/12/2004 11:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: JUNK IN HOLE @ 1333'. SANDED IN. IF GET 1200' OR MORE SPOT 50 SX CMT AT CUT OFF. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

*copy*

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE  
Date/Time Plugging Completed: 04/12/2004 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 2970'. WELL SANDED IN AT 1333'. 1ST PLUG LOAD HOLE WITH MUD. SPOT 25 SX CMT AT 1067' THROUGH TUBING. 2ND PLUG PULL TO 650' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
2896	2910		
2883	2887		

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 06 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY SARGENTS. RECOVERED 1041' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed \_\_\_\_\_

(TECHNICIAN)