

API NUMBER 15-009-15123-00-00

LEASE NAME Harzman VO

WELL NUMBER 6

4950 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 33 TWP. 16S RGE. 11 (E) or (W)

COUNTY Barton

Date Well Completed 6-20-42

Plugging Commenced 4-13-04

Plugging Completed 4-14-04

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Beredco, Inc.

ADDRESS P.O. Box 723, Hays, KS 67601

PHONE (785) 628-6101 OPERATORS LICENSE NO. 5147

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-12-04 (date)

by PAT STAAB (KCC District Agent's Name).

Is ACC-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arb Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3345

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>						
<u>Surf</u>						
<u>Prod</u>						
			<u>358</u>	<u>8.625</u>	<u>358</u>	<u>0</u>
			<u>3329</u>	<u>4.5</u>	<u>3329</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
Move in 2 3/8 tbg. Run open end tbg. to 2485'. Rig up Allied. Mix 85 sx 60/40 poz 10% gel w/300 # hulls. Pull tbg. to 1500'. Circ to surf. in 4 1/2 + 2 3/8 annulus + 8 5/8 x 4 1/2 annulus w/60 sx 60/40 poz 10% gel + 200 # hulls. Pull tbg. out of hole. Hook up to 4 1/2 csg. Circ cement w/20 sx. Shut in 8 5/8 surf pipe. press to 400# Shut in w/200#. Well plugged 4 PM witness Pat Staab KCC Hays 99998

Name of Plugging Contractor Berexco, Inc. Company Tools License No. 5363

Address P.O. Box 723, Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dennis Kirmer (Employee of Operator) or (Operator) o above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Dennis Kirmer


(Address) P.O. Box 723, Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 20th day of April, 2004

Marion Sue Vance  
 Notary Public

My Commission Expires: 4-30-06

RECEIVED  
 APR 30 2004  
 KCC WICHITA



KCC  
 Form 07-1  
 Revised 05-88  
 APR 28 2004  
 HAYS, KS

*pu*