

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-009-23,672000

LEASE NAME Harzman

WELL NUMBER 7

3686 Ft. from N Section Line

3630 Ft. from W Section Line

SEC. 33 TWP. 16S RGE. 11 (E) or (W)

COUNTY Barton

Date Well Completed 10-23-84

Plugging Commenced 4-13-04

Plugging Completed 4-14-04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Beredco, Inc.

ADDRESS P.O. Box 723, Hays, KS 67601

PHONE (785) 628-6101 OPERATORS LICENSE NO. 5147

Character of Well oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-12-04 (date)

by PAT STAAB (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Topeka-Lansing Depth to Top _____ Bottom _____ T.D. 3500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>			<u>784</u>	<u>10.75</u>	<u>784</u>	<u>0</u>
<u>Prod</u>			<u>3499</u>	<u>7.00</u>	<u>3499</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Run 2 3/8 open end tbg. to 2575' Rig up Allied. Mix 100 sx 60/40 po2 10% gel w/700# hulls. Pull tbg to 1500' Mix 150 sx 60/40 po2 10% gel w/200# hulls. Pull tbg to 800' Mix 110 sx 60/40 po2 10% gel w/100# hulls. Circ to surf in 7 x 2 3/8 annulus. Pull tbg out Hook up to 7" csg. Mix 165 sx 60/40 po2 10% gel - circ cement to surf. in 10 3/4 surf pipe. Shut in surf pipe. squeeze w/10 sx - max press 600# - shut in well w/500#. Well plugged 12 noon

Witness Pat Staab KCC Hays
Name of Plugging Contractor Berexco, Inc. Company Tools License No. 5363-9998

Address P.O. Box 723, Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dennis Kirmer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Dennis Kirmer

(Address) P.O. Box 723, Hays, KS 67601


SUBSCRIBED AND SWORN TO before me this 20th day of April, 2004

Marion Sue Vance

Notary Public

My Commission Expires: 4-30-06

KCC



Form CP-1
Revised 05-88

RECEIVED
APR 30 2004
KCC WICHITA