

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-30179-00-01
Comp. 1965

LEASE NAME Wilhaus

WELL NUMBER 1

660 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 35 TWP. 20 RGE. 7W (E) or (W)

COUNTY Rice

Date Well Completed _____

Plugging Commenced 4-16-04

Plugging Completed 4-16-04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RAMA OPERATING CO., INC.

ADDRESS P.O. Box 159 Stafford, Kansas 67578

PHONE#(620) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-8-04 (date)

by Mike Wilson (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3405'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	250'	None
				6"	3386'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Plugged off bottom with sand to 3330' and 6 sacks cement. Perforated 6" casing @1704', 600' and 300'. Ran 2" tubing 1075', pumped 50 sacks cement, pulled tubing up to 600' and pumped 50 sacks cement, pulled up to 300' and circulated 165 sacks cement up 6" and 8-5/8" to surface. Topped off with 20 sacks cement. 60/40Pos. 4% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 27th day of April, 20 04

Irene Herzberg
Notary Public

My Commission Expires: _____



RECEIVED

APR 30 2004

KCC WICHITA