

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-079-34825-00-00
API NUMBER Comp. 10-27-33
LEASE NAME AR Nikkel

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2
998 Ft. from S Section Line
998 Ft. from ^WSection Line

LEASE OPERATOR BIG "O"
ADDRESS 2820 Paseo Drive Great Bend, Kansas 67530

SEC. 8 TWP. 22 RGE. 3W (E) or (W)
COUNTY Harvey

PHONE# (620) 792-2868 OPERATORS LICENSE NO. 3942

Date Well Completed 10-29-1933

Character of Well Oil

Plugging Commenced 4-16-04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-20-04

The plugging proposal was approved on 3-19-04 (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3466'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Surf.</u>				<u>15-1/2"</u>	<u>282'</u>	<u>None</u>
<u>Prod</u>				<u>8-5/8"</u>	<u>3153'</u>	<u>None</u>
<u>Prod</u>				<u>5-1/2"</u>	<u>3430'</u>	<u>1230'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 2960' and 5 sacks cement. Shot pipe loose @1230', laved down 5-1/2" casing. Perforated 8-5/8" @550' and 330'. Ran 2" tubing down 8-5/8" to 550' and spotted 50 sacks cement. Pulled tubing to 330' and circulated 90 sacks. Tied onto 8-5/8" and pumped 140 sacks but didn't circulate up 15-1/2". Ran 1" down 15-1/2" to 325' and spotted 50 sacks cement. Tagged cement @305', mixed 50 sacks CC, 4% gel, pulled 1" out. Ran 2" tubing down 15-1/2" & circulated 225 sacks cement and 300# hulls. Ran 2" down 8-5/8" to 570' & circ. 155 sxs. 60/40 pos. 4% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524 Plugging Complete

Name of Party Responsible for Plugging Fees: BIG "O"

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 27th day of April, 2004

[Signature]
Notary Public

RECEIVED

APR 30 2004

KCC WICHITA My Commission Expires:

