

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-20119-00-00

LEASE NAME Wilhaus

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #3-Jan

660 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 35 TWP. 20 RGE. 7W (E) or (W)

COUNTY Rice

EASE OPERATOR RAMA OPERATING COMPANY, INC.

ADDRESS P.O. Box 159 Stafford, Kansas 67578

PHONE#(620) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well

Date Well Completed _____

Plugging Commenced 4-19-04

Plugging Completed 4-20-04

The plugging proposal was approved on _____ (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3416'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>				<u>8-5/8"</u>	<u>200'</u>	<u>None</u>
<u>Prod</u>				<u>5-1/2"</u>	<u>3405'</u>	<u>1220'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3350' and 5 sacks cement. Shot casing loose @1220', pulled up to 1075', pumped 35 sacks cement, pulled up to 600', pumped 35 sacks cement, pulled up to 300' and circulated 155 sacks cement to surface, 60/40 pos, 4% gel. Layed down rest of casing. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED
APR 30 2004

SUBSCRIBED AND SWORN TO before me this 27th day of April, 2004

[Signature]
Notary Public

KCC WICHITA My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-31-05