

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: H & B Petroleum Corporation
Address: P.O. Box 277, Ellinwood, Kansas 67526
Phone: (620) 564 - 3002 Operator License #: 32158
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 04-21-2004 (Date)
by: Dennis Hamel (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3823 Bottom: 3827 T.D. 3827

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 163-01774-00-00
Lease Name: Darrel
Well Number: 2
Spot Location (QQQQ): C - NE - NW - NW
330 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 34 Twp. 9 S. R. 20 East West
County: Rooks
Date Well Completed: 05-09-1950
Plugging Commenced: 04-22-2004
Plugging Completed: 04-22-2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Oil	3823	3827	5 1/2" 15.5#	May 1, 1950	Left in hole
<u>Surf</u>			<u>1759</u>	<u>8.625</u>	<u>1759</u>	<u>⊗</u>
<u>Prod</u>			<u>3823</u>	<u>5.5</u>	<u>3823</u>	<u>⊗</u>


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP at 3750'. Ran tubing to 3710'. Pump 285 sxs of 60/40 pos w/ 500# hulls from 3710' to surface. Circulate cement from casing leak at 1000' to surface, down 5 1/2" backside in 8 5/8". Cement to surface and squeeze to 300#. 450 sxs total cement and 700# hulls.

Name of Plugging Contractor: Allied Cementing License #: 99996 ~~Not required~~
Address: 24 South Lincoln St., Russell, Kansas 67665
Name of Party Responsible for Plugging Fees: H & B Petroleum Corporation
State of Kansas County, Barton, ss.
Al Hammersmith

RECEIVED
APR 26 2004
KCC WICHITA

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
(Address) P.O. Box 277, Ellinwood, Kansas 67526

SUBSCRIBED and SWORN TO before me this 23rd day of April, 2004
Lynnae M. Partridge My Commission Expires: January 3, 2006
Notary Public