

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20066-00-01  
Spot: NENW Sec/Twnshp/Rge: 3-21S-7W  
4620 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: PALLISTER Well #: 3  
County: RICE Total Vertical Depth: 4050 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S. MAIN  
STAFFORD, KS 67578

PROD Size: 7 feet: 3774  
SURF Size: 9 feet: 173

#131<sup>63</sup>

Well Type: SWD UIC Docket No: D13884.0 Date/Time to Plug: 04/13/2004 8:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Sand to 3,720' & top with 7 sxs. cement. Perforate 7" casing at 1,000', 500', & 260'. Run tubing to 1,000' & spot 50 sxs. cement. Pull tubing to 550' & spot 50 sxs. cement. Pull tubing to 260' & circulate cement of the surface.  
Plugging Method:

Plugging Proposal Received By: MICHAEL WILSON

Witness Type: PARTIAL

Date/Time Plugging Completed: 04/13/2004 5:00 PM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Sanded to 3,720' & topped with 7 sxs. cement. Perforated 7" casing at 1,000', 550', & 260'. Ran 2 3/8" tubing to 1,024' and spotted 50 sxs. cement. Pulled tubing to 576' & spotted 50 sxs. cement. Pull tubing to 288' & circulated 130 sxs. cement of the surface. Cement dropped to 70' and operator topped off with 20 sxs. cement on 04/20/04.

RECEIVED  
KCC DISTRICT #2

APR 27 2004

WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING CO. INC. INVOICE #18291

Plugged through: TBG

District: 02

Signed

*Michael R Wilson*

(TECHNICIAN)

INVOICED

DATE 5-5-04  
INV. NO. 2004061509