

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-01267-00-01
Spot: NENESW Sec/Twnshp/Rge: 20-33S-11W
2200 feet from S Section Line, 3080 feet from E Section Line
Lease Name: W A NEWKIRK Well #: 16
County: BARBER Total Vertical Depth: 4606 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

CIBP Size: feet: 3998 WITH 2 SX CMT
CIBP Size: feet: 4330 WITH 2 SX CMT *149⁷⁰*
PROD Size: 5.5 feet: 4606 WITH 250 SX CMT
SURF Size: 8.625 feet: 259 WITH 250 SX CMT

Well Type: SWD UIC Docket No: D19460.0 Date/Time to Plug: 04/13/2004 3:45 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4430' & 3998' WITH 2 SX CMT ABOVE EACH CIBP. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2004 4:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4565'. SET CIBP @ 4330' & PUT 2 SX CMT ON TOP OF CIBP. ALSO SET CIBP @ 3998' & PUT 2 SX CMT ON TOP OF CIBP. LAID DOWN 5 1/2" CASING & RUN 2 7/8" TUBING IN TO SPOT PLUGS THROUGH. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4512	4542		
4055	4075		

RECEIVED
MAY 03 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2200' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 5-5-04
INV. NO. 2004061501

Form CP 23 *[Signature]*