

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20342-00-00
Spot: NW Sec/Twnshp/Rge: 20-31S-36W
1500 feet from N Section Line, 1300 feet from W Section Line
Lease Name: MARTHA REYNOLDS B Well #: 2
County: STEVENS Total Vertical Depth: 2995 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PARKWA
HOUSTON, TX 77210

CIBP Size: feet: 2830
PROD Size: 5.5 feet: 2995 WITH 300 SX CMT
SURF Size: 8.625 feet: 611 WITH 300 SX CMT

#9734

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/12/2004 11:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: JUNK IN HOLE @ 1333'. SANDED IN. IF GET 1200' OR MORE SPOT 50 SX CMT AT CUT OFF. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 04/12/2004 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 2970'. WELL SANDED IN AT 1333'. 1ST PLUG LOAD HOLE WITH MUD. SPOT 25 SX CMT AT 1067' THROUGH TUBING. 2ND PLUG PULL TO 650' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

RECEIVED
MAY 03 2004
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
2896	2910		
2883	2887		

Remarks: USED 60/40 POZMIX 6% GEL BY SARGENTS. RECOVERED 1041' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

RECEIVED
APR 13 2004
KCC Dodge City

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 5-5-04
INV. NO. 2004061495

Form CP-2/B