

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20173-00-01
Spot: NENWSE Sec/Twnshp/Rge: 22-17S-27W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MERRITT ATWELL Well #: 1
County: LANE Total Vertical Depth: 4578 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N.
VALLEY CENTER, KS 67147

MSSC Size: feet: 1973 WITH 550 SX CMT
PKR Size: feet: 4047
PROD Size: 4.5 feet: 4268
SURF Size: 8.625 feet: 329

H 148 19

Well Type: EOR UIC Docket No: E26374.1 Date/Time to Plug: 04/20/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ALLEN WALKER Company: DAYSTAR PETROLEUM Phone: (316) 755-3523

Proposed Plugging Method: PUMP 300# HULLS & 30 SX CMT. GEL SPACER TO 2000' & CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2004 12:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4224'. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS. CMT AT SURFACE.
PRESSURED UP. PUMPED DOWN 4 1/2" 200# HULLS, 30 SX CMT, 12 SX GEL TO
2000' & 150 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4088	4160		

RECEIVED
MAY 03 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
APR 29 2004
KCC Dodge City

Signed Kevin D Strube
(TECHNICIAN)

INVOICED
DATE 5.5.04
INV. NO. 2004061493

Form CP 233 *[Signature]*