

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03236-00-01
Spot: SESENE Sec/Twnshp/Rge: 9-10S-25W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: ELRICK Well #: 10-2
County: GRAHAM Total Vertical Depth: 4245 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 8223 WILLOW PLACE SOUTH
HOUSTON, TX 77070

PROD Size: 5.5 feet: 4051 w/100 sxs cmt
SURF Size: 8.625 feet: 152 w/100 sxs cmt

137 96

Well Type: EOR UIC Docket No: E14576.5 Date/Time to Plug: 04/21/2004 9:30 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: NEIL PFANNENSTIEL Company: CITATION OIL & GAS CORP. Phone: (218) 517-7800

Proposed Plugging Method: Order 265 sxs cement - 9 sxs gel - 200# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2004 12:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report: Perfs:

Tubing to 3650' - spotted 20 sxs cement.
Pulled tubing to 3350' - spotted 9 sxs gel.
Pulled to 2200' - perforated at 2300' - circulated with 70 sxs cement and 100# hulls.
Pulled tubing to 1200' - perforated at 1300' - spotted 100 sxs cement with 100# hulls.
Pulled all tubing - squeezed 5 1/2" with 25 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.
Tied onto 8 5/8" x 4 1/2" - squeezed 25 sxs cement.
Max. P.S.I. 100#. S.I.P. 100#.
Total of 240 sxs 60/40 pozmix - 9 sxs gel and 200# hulls.

RECEIVED
MAY 03 2004
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS RIEDEL B-2. ALLIED CEMENTING COMPANY, PFEIFER & CHEYENNE WELL SERVICES-WATER.

Plugged through: TBG

District: 04

Signed Roger Moses
(TECHNICIAN)

INVOICED

DATE 5-5-04
INV. NO. 2004061490

APR 28 2004

EMPIRE DRLG & N G R A #2 RIEDEL 'B' 9-10-25W
SE SE NE

Contr. EMPIRE DRLG GRAHAM County

E. 2526RB Comm. Comp. 10-24-58 IP 193 BOPD
PHY POT

Tops	Depth	Datum	Casing
ANH	2152	374	8" 152 5" 4051
HEEB	3754	-1228	DST 1722-42/10", 300' SND & 300' SW
TOR	3777	-1251	
LANS	3792	-1266	DST 3764-90/1 HR, 1980' G, 655' CL 0, 65' V H OCM, BHP 1360#
B/KC	4030	-1504	DST 3985-4010/1 HR, 5-10' V H OCM, 180' MCO, 60' O, 520#
CHERO	4225	-1699	DST 4234-45/1 HR, 25' MDY W, ELRICK NW .SCM 0, BHP 0#
TD	4245	-1719	PERF 24/3999-4005: 5 BOPH: ACID 3000: 36 BOPH/1 HR: SWB 46 BOPH/6 HR

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

+	+	+
+	+	+
+	+	+