

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-33287-00-00
Spot: SWSENW Sec/Twnshp/Rge: 36-24S-15W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: SATTERLEE Well #: 3
County: STAFFORD Total Vertical Depth: 4476 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

PROD Size: 5.5 feet: 4476 WITH 125 SX CMT
SURF Size: 8.625 feet: 280 WITH 290 SX CMT

8/145 47

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/15/2004 5:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 4350' & 5 SX CMT. PLUG AT 960' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG
Date/Time Plugging Completed: 04/15/2004 7:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 4451'. ANHYDRITE @ 960'. SANDED TO 4350' & 5 SX CMT WITH DUMP BAILER. PERFORATE AT 960'. RUN TUBING TO 960'. PUMP 21 BBL CMT TO SURFACE UP 2 3/8" X 5 1/2". SLIGHT BLOW ON 5 1/2" X 8 5/8" ANNULUS. PULL TUBING OUT OF HOLE. PUMP DOWN 5 1/2". PUMPED 16 BBL CMT TO SURFACE. PUMPED A TOTAL OF 290 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4406	4410		

RECEIVED
MAY 03 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed _____

[Signature]
(TECHNICIAN)

INVOICED
DATE 5-5-04
INV. NO. 2004061-513

Form *[Signature]*