

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-01273-00-00
Spot: SESENW Sec/Twnshp/Rge: 20-33S-11W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease Name: NEWKIRK Well #: 22
County: BARBER Total Vertical Depth: 4610 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

CIBP Size: feet: 4190 WITH 2 SX CMT
CIBP Size: feet: 4240
PROD Size: 5.5 feet: 4609 WITH 100 SX CMT
SURF Size: 8.625 feet: 286 WITH 250 SX CMT

14983

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/23/2004 9:45 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4240' WITH 2 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 0-60' WITH 20 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/23/2004 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4190' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID CASING DOWN & RAN 2 7/8" TUBING IN TO SPOT PLUGS THROUGH. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4522	4534		
4480	4510		

RECEIVED
MAY 03 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3100' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 5-5-04
INV. NO. 2004061561

FORM CP-305